

United States Department of the Interior
National Park Service

For NPS use only

National Register of Historic Places
Inventory—Nomination Form

received

date entered

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections**1. Name**

historic Peabody Township Carnegie Library

and or common Same

2. Location

street & number 214 Walnut

___ not for publication

city, town Peabody

___ vicinity of

state Kansas

code 20

county Marion

code 115

3. Classification

Category	Ownership	Status	Present Use
___ district	<input checked="" type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	___ agriculture
<input checked="" type="checkbox"/> building(s)	___ private	___ unoccupied	___ commercial
___ structure	___ both	___ work in progress	<input checked="" type="checkbox"/> educational
___ site	Public Acquisition	Accessible	___ entertainment
___ object	N/A in process	<input checked="" type="checkbox"/> yes: restricted	___ government
	N/A being considered	___ yes: unrestricted	___ industrial
		___ no	___ military
			___ other:

4. Owner of Property

name Peabody Township

street & number 300 N. Walnut

city, town Peabody

___ vicinity of

state Kansas 66866

5. Location of Legal Description

courthouse, registry of deeds, etc. Marion County Clerk

street & number Marion County Courthouse

city, town Marion

state Kansas 66861

6. Representation in Existing Surveys

title N/A

has this property been determined eligible? ___ yes ☒ no

date N/A

___ federal ___ state ___ county ___ local

depository for survey records N/A

city, town N/A

state N/A

7. Description

Condition

☒ excellent
☐ good
☐ fair

☐ deteriorated
☐ ruins
☐ unexposed

Check one

☐ unaltered
☒ altered

Check one

☒ original site
☐ moved date _____

Describe the present and original (if known) physical appearance

The Peabody Township Carnegie Library (c. 1914) is located at 214 Walnut in Peabody, Marion County, Kansas (pop. 1,474). The one-story, brick, Neo-Classical building stands on a corner lot one block north of Peabody's central business district. Its facade orientation is west. The building measures approximately fifty-six feet from north to south and forty feet from east to west. It retains its original function as a library.

The one-story, grey brick building sits on a raised foundation with a limestone base. It is a rectangular structure with a ridge hipped roof. Three bays comprise the building's facade and rear, it is one bay deep. A parapetted entryway pavilion projects from the facade's center bay. A masonry entablature comprised of a multiply moulded limestone architrave, a brick frieze, and a multiply moulded, dentilled, limestone cornice concludes the wall treatment on the facade, north and south elevations. The original roofing material has been replaced with asphalt or fiberglass shingles, probably in 1979.

The projecting entryway pavilion contains a recessed, transomed, double door surmounted by a cornice and a pair of stained glass windows. Double screen doors front the main wood and glass doors, both sets of doors appear to be original. An original clear glass transom surmounts the door. A limestone frieze bearing the inscription "Carnegie" stands above the transom, surmounted by a multiply moulded limestone cornice supported by scrolled limestone consoles. Two rectangular stained glass windows with wooden frames pierce the wall above the cornice, underscored by a thick limestone sill. The multi-colored dark glass is arranged in a repeating geometric design. These windows are original.

The brick pillars which form the pavilion support a limestone frieze bearing the carving "Peabody Library". The aforementioned cornice surmounts the frieze, which is in turn, surmounted by the pavilion's parapet. Two brick end blocks with limestone capping flanked by a limestone balustrade form the parapet. Limestone Doric capitals mark the pillars, the capitals merge with the building's limestone architrave. A carved limestone wreath with an open book inside of it ornament each pillar below its capital. A flush limestone tablet underscored by a recessed limestone table stand beneath each wreath. An arched recession with brick upper surrounds stand beneath the tablets on each pillar. A cast iron light sconce with a milk glass bowl projects out of each recession. Stone steps lead up to the doorway. These treatments are original.

Two identical window bays flank the facade's pavilion. Slightly recessed wall space holds the first and basement level fenestration. The recessions are flanked by pillar like wall units that emanate from a limestone base and conclude in the building's entablature. A tripartite, 1/1 double hung window unit with stained glass transoms pierces the first level wall space of each bay. A limestone sill which runs the length of the recession underscores the windows. The stained glass transoms employ the same multi-colored, dark glass and repeating geometric design as the pavilion windows do. A single brick course marks the top of the recession, jointing just below the building's architrave. A tripartite, 1/1 double hung window unit pierces the foundation below the first level windows. A single brick course marks the recession above the basement level

United States Department of the Interior
National Park Service

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only

received

date entered

Continuation sheet 1

Item number 7

Page 1

windows. Aluminum frame storm windows cover the original wooden framed windows but the transoms are exposed.

Three, 1/1 double hung windows with transoms and limestone sills fenestrate the first level of the north elevation. The two most western transoms are stained glass, employing the same multi-colored, dark glass and repeating geometric design as the pavilion and The facade transom windows do. The most eastern transom is clear glass. Aluminum framed storm windows cover the original wooden window frames but the transoms are exposed. One-over-one, double hung windows with brick lintels pierce the foundation below the first level windows. A basement door surmounted by a limestone pediment pierces the center east part of this elevation.

Three small groups of tripartite, 1/1 double hung windows pierce the upper wall space of the southern elevation. Detached limestone lintels surmount the window groupings, limestone sills underscore them. A pair of 1/1 double hung windows with aluminum framed storm windows pierce the foundation's outer wall space on the southern elevation. Brick lintels surmount the windows, limestone sills underscore them.

Eight, 1/1 double hung windows with stained glass transoms pierce the first level wall space of the rear elevation. Jack arches surmount the windows, limestone sills underscore them. The multi-colored, dark stained glass and repeating geometric design used for the transoms is found on the transoms throughout the building. Aluminum framed storm windows cover the original wooden sashes but the transoms are exposed. Smaller, 1/1 double hung windows with jack arches pierce the foundation, below some of the first level windows.

The interior of the building retains its original floor plan and vestibule entrance. The first floor ceiling retains its beaming. The interior woodwork, such as door and window surrounds, is retained as are the original tables and chairs.

8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input checked="" type="checkbox"/> education	<input type="checkbox"/> military	<input checked="" type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates c. 1914

Builder/Architect A.A. Crowell - Architect
M.R. Stauffer - Builder

Statement of Significance (in one paragraph)

The Peabody Township Carnegie Library (c. 1914) is being nominated to the National Register as part of the Carnegie Libraries of Kansas thematic resources nomination (c. 1902-1921) at the local level of significance under criteria A and C for its historical association with the Carnegie Corporation Library Building Program and for its architectural significance as a new building type. A library association was organized in Peabody in 1874. The community received their \$10,000.00 Carnegie Library grant in 1913, library construction was completed in 1914. The Peabody Township Carnegie Library is an example of the Neo-Classical style.

Sixty-three Carnegie funded libraries were built in Kansas during the first three decades of the Twentieth Century; four of these libraries were built on college campuses. In most cases, the Carnegie funded library represented the community's first library building although many Kansas communities had book clubs and library organizations well before the Carnegie Corporation Library Building Program was founded. In the case of the four college libraries, the building represented the first structure which was solely devoted to housing the institution's books and providing study space. Carnegie did not solicit interest in the program, with the exception of the Anderson (Carnegie) Memorial Library which was built by Carnegie as a memorial to his friend John Anderson and was the first college library nationally to receive Carnegie funding. Communities initiated contact with the corporation by letter, indicating their desire for a Carnegie funded library. If the Corporation responded favorably to the request, a firm local commitment to the program's requirements, which generally resulted in a public election in support of the library, followed. Obviously these actions represented a perceived need within the community for a library building and the Carnegie Corporation Library Building Program represented an excellent way to secure the funds to build one. Many of the Carnegie Libraries built in Kansas reflect the high space utilization design guidelines promoted by the Carnegie Corporation after 1910, underscoring the point that before the Carnegie Corporation Library Building Program, few architects and/or builders had experience designing this building type.

Twenty-eight Carnegie Libraries are included in this nomination (see inventory). Twelve Carnegie Libraries have been listed individually on the National Register: Argentine, Case Library (Baker University, Baldwin City), Caldwell, Dodge City, Emporia, Goodland, Lawrence, Leavenworth, Newton, Ottawa, Parsons, and Pittsburg. The Carnegie Library at Arkansas City is included in a downtown historic district. Thirteen Carnegie Libraries have been demolished: Great Bend, Halstead, Hays, Iola, Kansas City, McPherson, Morrison Library (Fairmont College, Wichita), Olathe, Osawatimie, Plainville, Russell, Salina, and Washington. Five Carnegie Libraries have been altered enough to make them ineligible for the National Register: Abilene, Garden City, Hiawatha, Lyons, and Stockton. (The nominations for the Concordia, Eureka, Independence, and Winfield libraries were deferred.) Twenty-two of the nominated libraries retain their original function. All of the buildings are in use or have an active use planned for them. The

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only
received
date entered

Continuation sheet 2

Item number 8

Page 1

nominated libraries maintain a high to moderate degree of architectural and structural integrity.

Industrialist Andrew Carnegie (1835-1919) and the Carnegie Corporation significantly influenced the development and expansion of public library systems worldwide. Between 1886 and 1921 Carnegie funds assisted in the construction of 1,681 city and 108 college libraries in the United States. As a region, the Mid-West, Kansas included, did not have a well established public library system until the Carnegie Program and ranks highest in the number of communities which obtained Carnegie Libraries nationwide. Out of the forty-six states to participate in the library building program, Kansas ranks approximately eleventh in the number of Carnegie Libraries built. For many Kansas communities, the Carnegie Library represented its first library building, providing an environment that all members of the community could share for the purposes of reading, learning, and education.

Eligibility for Carnegie Library funds rested on several factors. Firstly, the population of the community had to exceed 1,000; in Kansas this indicated at least a second class city status. This population requirement generally resulted in county seat communities applying for and receiving Carnegie Libraries. Some communities with populations less than 1,000 banded together with neighboring communities to achieve the 1,000 mark and applied for township libraries, as in the case of the Peabody and Canton Township libraries. In the case of college libraries this constraint may not have applied, although the four Kansas colleges to receive Carnegie libraries were located in cities which had populations in excess of 1,000 by 1900. Secondly, the applicant had to provide a site for the library. The sites tended to be one or two blocks outside of the community's main business district. Thirdly, the applicant had to provide an annual endowment for the maintenance and improvement of the library which amounted to at least ten percent of the initial grant from the Carnegie Corporation.

This last factor contributed to the ending of the Carnegie Library Building Program in 1917, although grants for books and other improvements continued for several more decades. An inherent problem for second class cities in Kansas was the .4 mill levy restriction for libraries, making it difficult for some communities to meet the annual ten percent maintenance appropriation solely through public dollars. In 1917 the Kansas State legislature increased the library levy to .5 mill for second and third class cities, an amendment which affected most of the communities in the State that had Carnegie Libraries. In 1916, large communities such as Topeka, Wichita, Hutchinson, and Leavenworth had library mill levies of 1.06, 1.2, 1.8, and 3.5 respectively. In Kansas, the average public library grant was \$12,000 and the average college library grant was \$37,000. These monies covered the cost of the building, the necessary furniture and fixtures, and the architects' fees.

Prior to 1910, the Carnegie Corporation did not provide design guidelines for the libraries that it funded and because the library was a relatively new building type, few architects and/or builders had experience with its design. Many of the early libraries

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only

received

date entered

Continuation sheet 3

Item number 8

Page 2

were expensive examples of the Beaux Arts style with little focus on floor plan and space efficiency. In 1910, Carnegie's personal secretary James Bertram developed model specifications and floorplans for proposed libraries, entitling his work Notes on Library Buildings. The Notes on Library Buildings provided the first widely circulated guidelines for library design in this country.

Bertram wrote:

Small libraries should be pland (sic) so that one librarian can oversee the entire library from a central position.... The bilding (sic) should be devoted exclusively to: (main floor) housing of books and their issue for home use; comfortable accomodations for reading them by adults and children; (basement) lecture room; necessary accommodation for heating plant; also all conveniences for the library patrons and staff. Experience seems to sho (sic) that the best results for a small general library are obtained by adopting the one-story and basement rectangular type of bilding (sic), with a small vestibule entering into one large room sub-divided as required by means of bookcases.... The rear and side windows may be kept about six feet from the floor, to giv (sic) continuous wall space for shelving. A rear wing can be added for stack-room (when future need demands it) at a minimum expense, and without seriously interfering with the library servis (sic) during its construction. The site chosen should be such as to admit lite (sic) on all sides, and be large enuf (sic) to allow extension, if ever such should become necessary.

The thirty-six Carnegie Libraries built in Kansas after 1910 reflect Bertram's precedents, exhibiting high space utilization, and often including full basements, although the raised basement is a design element employed in the earlier libraries as well. Most of these one-story libraries exhibit a three bay, Neo-Classical facade with a projecting central pedimented entry pavilion and are one bay deep. The use of native limestone is evident in some of the libraries but the most common material combination is brick with a limestone foundation. While there is some tendency toward a vernacular interpretation to the design ornamentation of these libraries, the general approach verges on high style.

Correspondence between the Carnegie Corporation and the library boards from the Kansas communities that received Carnegie Libraries indicates that the designs for these libraries were carefully scrutinized by Bertram and in many cases, were resubmitted several times before meeting his requirements. Upon the completion of a library, the library board was instructed to send a full set of blueprints and elevations of the building to the Corporation. However, recent correspondence between the Kansas State Historical Society and the Carnegie Corporation reveals that the Corporation does not have blueprints of the Kansas libraries. The Corporation does have some library photographs but the collection is not inclusive.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only

received

date entered

Continuation sheet

4

Item number 8

Page 3

Three architects were particularly active in the design of Kansas Carnegie Libraries: George P. Washburn of Ottawa, Kansas designed nine, A. T. Simmons of Bloomington, Illinois designed six, and William Warren Rose of Kansas City, Kansas designed four. Washburn's libraries are primarily of the standard three-bay, Neo-Classical variety. His firm is credited with the Carnegie libraries in Burlington, Canton, Cherryvale, Columbus, Eureka, Halstead, Osawatomie, Ottawa, and Sterling. Simmons engaged in a more eclectic approach, designing libraries in Abilene, Chanute, Council Grove, Downs, Hays and Yates Center. Rose is credited with the classically inspired libraries in Argentine, Kansas City, Manhattan, and Newton. In Kansas, many Kansas based architects were commissioned to design Carnegie Libraries as well as architects from Illinois, Missouri, Nebraska, and Texas.

Today, many of the state's Carnegie Libraries are facing serious space shortages. The alternatives of adding on or vacating both present preservation problems. Additions to these libraries must be such that the building's original character is not altered. Vacating the library for a larger facility leaves the problem of an empty building, in some communities county historical societies have inherited the empty Carnegie Library. In any event, when these buildings are no longer recognized from a design standpoint as Carnegie Libraries, their architectural significance ceases.

Inventory of Carnegie Libraries in Kansas

<u>SITE</u>	<u>DATE</u>	<u>INVENTORY NUMBER</u>
1. Anthony Public (Carnegie) Library (Harper County) 104 N. Springfield Anthony, Kansas 67003 Owner: City of Anthony Lots 22,23,24; Block 34.	c. 1911	⁰⁰⁰⁴ 77-0180-0003
2. Burlington Carnegie Free Library (Coffey County) 201 N. Third Burlington, Kansas 66839 Owner: City of Burlington Lots 8,9; Block 35.	c. 1912	31-0690-0015
3. Canton Township Carnegie Library (McPherson County) Box 336 Canton, Kansas 67428 Owner: Canton Township Lots 7,8,9,10,11; Block 2.	c. 1921	113-0790-0001
4. Chanute Public (Carnegie) Library (Neosho County) 102 S. Lincoln Chanute, Kansas 66720 Owner: City of Chanute Lots 2,3; Block 39.	c. 1906	133-0870-0067
5. Cherryvale Public (Carnegie) Library (Montgomery County) 329 E. Main Cherryvale, Kansas 67335 Owner: City of Cherryvale Lots 7,8; Block 39.	c. 1913	⁰⁹³⁰⁻⁰⁰⁰⁵ 125-0939-0006
6. Clay Center Carnegie Library (Clay County) 706 Sixth Street Clay Center, Kansas 67432 Owner: City of Clay Center Lots 12,13; Block 36.	c. 1912	27-0980-0008

- | | | |
|---|---------|-----------------------|
| 7. Coffeyville Carnegie Public Library Building
(Montgomery County)
415 West 8th
Coffeyville, Kansas 67337
Owner: City of Coffeyville
Lots 7,8; Block 47. | c. 1912 | 1050
125-2670-0019 |
| 8. Columbus Public (Carnegie) Library (Cherokee County)
205 N. Kansas
Columbus, Kansas 66725
Owner: City of Columbus
Lots 9,10; Block 9. | c. 1913 | 21-1100-0008 |
| 9. Council Grove (Carnegie) Library (Morris County)
303 W. Main Street
Council Grove, Kansas 66846
Owner: City of Council Grove
Lots 1,2,3; Block 19. | c. 1917 | 127-1180-0074 |
| 10. Downs Carnegie Library (Osborne County)
504 S. Morgan
Downs, Kansas 67437
Owner: City of Downs
Lots 8-12; Block 28. | c. 1906 | 141-1400-0002 |
| 11. El Dorado Carnegie Library Building (Butler County)
101 S. Star
El Dorado, Kansas 67042
Owner: Dean Seeber
N 4' Lot 3, Lot 4; Block 4. | c. 1912 | 15-1540-0004 |
| 12. Anderson (Carnegie) Memorial Library (Lyon County)
The Way College of Emporia
1300 West 12th Avenue
Emporia, Kansas 66801
Owner: Way College of Emporia
Located on the Way College of Emporia campus.
SW, NE1/4, Sec. 9, T19, R11, E. of the 6th p.m.,
running thence E. 76 rods, thence N. 80 rods,
thence W. 76 rods, thence S 80 rods to the | c. 1902 | 111-1660-0002 |

Anderson (Carnegie) Memorial Library (Lyon County) cont.

place of beg., except a tract beg. at the S,SW1/4
Sec. 9, thence N. 670 ft., thence E. 540 ft.,thence
S. 250 ft, thence W. 374 ft., thence S. 420 ft.,
thence W. 166 ft. to the point of beg. in Lyon Co.,KS
and Lots Numbered 61,63,65,67,71, and the N. 30 ft. of
Lot F all in Block numbered 3, in College Hill Addition
to the City of Emporia.

- | | | |
|---|------------------|---------------|
| 13. Fort Scott Public (Carnegie) Library (Bourbon County)
201 South National
Fort Scott, Kansas 66701
Owner: City of Fort Scott
Lots 1,(N1/2) 3; Block 123 | c. 1902 | 11-1830-0016 |
| 14. Girard Carnegie Library (Crawford County)
128 W. Prairie
Girard, Kansas 66743
Owner: City of Girard
Lots 17,18; Block 14. | c. 1906 | 37-2050-0003 |
| 15. Herington Carnegie Public Library (Dickinson County)
102 S. Broadway
Herington, Kansas 67449
Owner: City of Herington
Lots 2,4; Block 40. | c. 1915 | 41-2420-0006 |
| 16. Hutchinson Public (Carnegie) Library Building-
Labor Temple (Reno County)
427 N. Main
Hutchinson, Kansas 67501
Owner: Hutchinson Labor Building Association
Lots 13,14,15; Block 17. | c. 1903-
1904 | 155-2660-0011 |
| 17. Kingman Carnegie Library (Kingman County)
455 N. Main
Kingman, Kansas 67068
Owner: City of Kingman
Lots 101,103,105; Original Town. | c. 1914 | 95-2850-0006 |

- | | | |
|---|---------|---------------|
| 18. Lincoln Carnegie Library (Lincoln County)
203 S. Third
Lincoln, Kansas 67455
Owner: City of Lincoln
Lot 7; Block 32. | c. 1914 | 105-3189-005 |
| 19. Lyndon Carnegie Library (Osage County)
127 E. Sixth, P.O. Box 563
Lyndon, Kansas 66451
Owner: Valleybrook Township
Lots 4-9; Block 22. | c. 1911 | 139-3360-0003 |
| 20. Manhattan Carnegie Library Building (Riley County)
Fifth and Poyntz
Manhattan, Kansas 66502
Owner: Riley County Board of Commissioners
Lot 413; Ward 2. | c. 1904 | 161-3490-0016 |
| 21. Osborne Public (Carnegie) Library (Osborne County)
Third and Main
Osborne, Kansas 67473
Owner: City of Osborne
All of Block 12. | c. 1913 | 141-4230-0006 |
| 22. Oswego Public (Carnegie) Library (Labette County)
704 Fourth Street
Oswego, Kansas 67356
Owner: City of Oswego
Lots 1,2,3,4; Block 32. | c. 1912 | 99-4250-0010 |
| 23. Peabody Township Carnegie Library (Marion County)
214 Walnut
Peabody, Kansas 66866
Owner: Peabody Township
Lots 80,82,84 on Walnut. | c. 1914 | 115-4410-0024 |
| 24. Sterling Free Public (Carnegie) Library (Rice County)
132 N. Broadway
Sterling, Kansas 67579
Owner: City of Sterling
Lots 182,184,186,188 on Broadway. | c. 1917 | 159-5225-0006 |

25. Washburn University Carnegie Library Building
(Shawnee County) c. 1904 177-5400-0017
(Education Building)
Topeka, Kansas 66621
Owner: Washburn University of Topeka
SW1/4, NW 1/4, NE 1/4, SW1/4, S1,T12, R15E
26. Wellington Carnegie Library (Sumner County) c. 1916 191-5730-⁰⁰¹³~~0012~~
121 W. Seventh
Wellington, Kansas 67152
Owner: City of Wellington
Lots 13,14,15,16,17; Block 53.
27. Wichita City (Carnegie) Library Building c. 1915 173-5880-0004
(Sedgwick County)
220 S. Main Street
Wichita, Kansas 67202
Owner: City of Wichita
Lots 24,26,28,30,32,34,36 & 1/2 Vac. Alley Adj.
on E. & Vac. Alley Ly. N. Lot 24 Exc. Beg. SE Cor.
Lot 34 W 33.98 Ft. N. 100.56 Ft. W. 16.75 Ft. N. 9 Ft.
Nwly. 15.36 Ft. W. 6.5 Ft. N. 10 Ft. W. 49 Ft. S. 25
Ft. W. 25 Ft. N. 58.66 Ft. E. to Cen. Li. Vac. Alley
on E. Th. S. 115.56 Ft. W. 8 Ft. to SE Cor. Lot 30 S.
to Beg. Main St. Greiffenstein's Add.
28. Yates Center (Carnegie) Library (Woodson County) c. 1912 207-6010-0007
218 N. Main
Yates Center, Kansas 66783
Owner: City of Yates Center
Lots 4,5,6; Block 27.

9. Major Bibliographical References

See attached sheet.

10. Geographical Data

Acreage of nominated property Less than 1 acre

Quadrangle name Peabody

Quadrangle scale 1:24,000

UTM References

A

1	4	6	6	5	7	6	0	4	2	2	6	1	2	0
---	---	---	---	---	---	---	---	---	---	---	---	---	---	---

Zone Easting Northing

B

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

Zone Easting Northing

C

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

D

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

E

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

F

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

G

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

H

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification The nominated property stands on Lots 80, 82, 84; Walnut Street (N-even) in Peabody, Kansas. The rectangular tract is bounded by Walnut to the west, Division to the north, and adjacent property lines to the east and south.

List all states and counties for properties overlapping state or county boundaries

state N/A code N/A county N/A code N/A

state N/A code N/A county N/A code N/A

11. Form Prepared By

name/title Martha Gray Hagedorn, Architectural Historian

organization Kansas State Historical Society

date April 15, 1987

street & number 120 West 10th Street

telephone 913-296-5264

city or town Topeka

state Kansas 66612


12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

☐ national ☐ state ☒ local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

State Historic Preservation Officer signature



title Executive Director, Kansas State Historical Society

date April 15, 1987

For NPS use only

I hereby certify that this property is included in the National Register

date

Keeper of the National Register

Attest:

date

Chief of Registration

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only
received
date entered

Continuation sheet

5

Item number

9

Page

1

Carnegie Library Bibliography:

Anderson, Florence. Carnegie Corporation Library Program, 1911-1961.
(New York: Carnegie Corporation, 1963).

Bertram, James. Notes on Library Building. (New York: Carnegie Corporation, 1910).

Bobinski, George S. Carnegie Libraries: Their History and Impact on American Public Library Development. (Chicago: American Library Association, 1969).

Carnegie Corporation. Micro-film reels of correspondence between the Corporation and Kansas Carnegie Library Communities, 1902-1921. Carnegie Corporation of New York.


Gardiner, Allen. The Carnegie Legacy in Kansas: A Retrospective View of the 59 Public Libraries Built by Andrew Carnegie; A Souvenir Publication to Commemorate the Sequicentennial of Carnegie's Birth. (Topeka: Kansas State Library, 1985).

_____. Kansas Public Libraries from Abilene to Zenda. (Topeka: Kansas State Library, 1982).

Koch, T. W. A Book of Carnegie Libraries. (New York: H. W. Wilson, 1917).

State of Kansas. Session Laws, 1917. Chapter 113. "Limiting Tax Levies in Cities of the Second and Third Class."

Topeka Capital Journal, 20 December 1916; 26 December 1916.



32

Peabody Carnegie Library
Peabody, Kansas
UTM Coordinates
14 665 760 4226 120

T. 21 S.
NEWTON 16 MI.
WALTON 8.6 MI.

